

ENERGY STAR Automatic Commercial Ice Makers Test Method Webinar

February 1, 2012

Christopher Kent, U.S. Environmental Protection Agency Ashley Armstrong, U.S. Department of Energy

ENERGY STAR Program



Agenda



1 Introduction
2 DOE Test Procedure
3 ENERGY STAR Test Method
4 Next Steps



EPA-DOE Memorandum of Understanding (MOU)



 On September 30, 2009, EPA and DOE signed a memorandum of understanding (MOU) designed to enhance and strengthen the ENERGY STAR program

EPA: Brand Manager	DOE: Technical Support
 New Products Performance Levels Marketing & Outreach Product Database Monitoring & Verification 	Test MethodsMetricsMonitoring & Verification



ENERGY STAR ACIM Program Development



- Updated ENERGY STAR Specification published Jan. 20th
 - References recently published DOE Test Procedure Final Rule*
- Published new ENERGY STAR Test Method Jan. 20th
 - Broadens scope of metrics and proposes test approach for products not covered by DOE

*10 CFR 431 Subpart H, Automatic Commercial Ice Makers. 77 FR 1591, January, 11 2012.



Agenda



1 Introduction
2 DOE Test Procedure
3 ENERGY STAR Test Method
4 Next Steps



DOE Test Procedure



- DOE test procedure final rule published January 11, 2012
 - Compliance date for testing: January 7, 2013
 No longer open for comment
- DOE test procedure changes
 - Updates references to industry test procedures
 - AHRI 810-2007 with Addendum 1
 - ASHRAE 29-2009
 - Includes method of test for continuous type ice makers
 - Provides normalization equation for ice hardness
 - Discontinues energy use rate calculation
 - Energy consumption per 100 pounds of ice



DOE Test Procedure



- Two issues not included in DOE test procedure final rule
 - Potable Water
 - DOE will not regulate or require testing and reporting of the potable water use of automatic commercial ice makers at this time. 77 FR 1605.
 - Remote Rack Compressor Connected Units
 - Remote condensing automatic commercial ice makers that are sold exclusively to be connected to remote compressor racks do not meet the definition of an automatic commercial ice maker set forth under 42 U.S.C. 6311(19) and, as such, are not subject to DOE regulations. 77 FR 1600.



Agenda



1 Introduction
2 DOE Test Procedure
3 ENERGY STAR Test Method
4 Next Steps



ENERGY STAR Test Method



- ENERGY STAR Draft 2 Specification referenced AHRI 810-2007
- New stand-alone ENERGY STAR test method
 - Published January 20, 2012
 - Includes changes described in Draft 2 specification
 - Includes additional sections related to:
 - Potable Water
 - Remote Rack Connect Units



Overview of Proposed Changes



- References DOE Test Procedure Final Rule*
- Revises Potable Water Requirements
 - Drafted definition for "variable purge setting"
 - Specified setting for units with variable purge settings
- Adds Remote Rack Compressor Units to ENERGY STAR Scope
 - Proposes two methods for testing remote rack connected units for comment

^{* 10} CFR 431 Subpart H, Automatic Commercial Ice Makers. 77 FR 1591. January 11, 2012.



Potable Water Requirements



- Variable purge setting not previously specified
- Drafted definition for "variable purge setting":

"A setting that allows for the increase or decrease of purge water used during ice making to accommodate for different water hardness levels."

- Updated to AHRI 810-2007 with Addendum 1
 - Potable water test method
 - Test setting for variable purge units



Remote Rack Compressor Units



 Expands scope to include units designed for connection only to remote rack compressors

	ENERGY STAR Scope
DOE Covered	 Air-cooled Batch and continuous type units Ice Making Heads Remote Condensing Units with dedicated condensing units Self-contained Units
Non-DOE Covered	 Air-cooled Batch and continuous type units RCUs designed for connection to remote rack compressors only

 Proposes two methods for testing remote rack connected units



Remote Rack Compressor Units – Proposal #1 (Designated RCU)



Test Setup

- Test units with a designated remote condensing unit (RCU)
- Manufacturers must provide an appropriately sized RCU
- RCU must be least efficient model available

Test Method

 Test units according to 10 CFR Part 431 Subpart H for units with dedicated remote condensers

Reporting

 Report energy consumption of ice maker, compressor, and condenser together



Remote Rack Compressor Units – Designated RCU - Feedback



- Are these units normally operated using an evaporator pressure regulator?
- How should "appropriate sizing" be determined?
- How does over/under-sizing affect ice making performance?
- How does operating with a dedicated RCU affect ice making performance and energy consumption compared to a remote rack compressor?



Remote Rack Compressor Units – Proposal #2 - Remote Rack



- Test Setup
 - Test units with a remote rack compressor
- Test Method ASHRAE 72-2005 approach*
 - Take measurements at coolant inlet and outlet
 - Determine total cooling provided to ice maker
 - Use default factor to calculate compressor energy consumption
- Reporting
 - Report energy consumption of ice maker and calculated compressor energy together

^{*} ASHRAE 72-2005 Method of Testing Commercial Refrigerators and Freezers



Remote Rack Compressor Units - Remote Rack - Feedback



- How should the default factors be determined?
 - Are the factors from commercial refrigeration equipment (CRE) applications applicable?
- Do test facilities have remote rack compressors already available to use for testing?
- How does size of remote rack compressor affect ice making performance?



Remote Rack Compressor Units - Comparison



	Advantages	Disadvantages
Designated RCU	 Repeatability Provides direct comparison between product types Uses DOE ACIM test procedure 	Cost of purchasing dedicated RCUSizing concerns
Remote Rack	 May provide better representation of energy consumption on a per model basis No dedicated RCU needed 	 Reference another DOE test procedure (likely CRE) May increase test burden Requires default factors for calculations



Additional Feedback?





Agenda



1 Introduction
2 DOE Test Procedure
3 ENERGY STAR Test Method
4 Next Steps



Timeline



Test Method Webinar	February 1, 2012
Deadline for Written Comments on Draft Test Method	February 10, 2012
Draft 2 Test Method to Stakeholders (if necessary)	March 2012
Draft Final Version 2.0 Specification to Stakeholders	March 2012



Contact Information



Please send any additional comments to icemachines@energystar.gov or contact:

Christopher Kent
EPA ENERGY STAR Program
Kent.Christopher@epa.gov

Ashley Armstrong
DOE ENERGY STAR Program
Ashley.Armstrong@ee.doe.gov

Erica Porras
ICF International
eporras@icfi.com

Kurt Klinke
Navigant Consulting, Inc.
Kurt.Klinke@navigant.com



